

क्षेत्रीय जैवप्रौद्योगिकी केन्द्र  
REGIONAL CENTRE FOR BIOTECHNOLOGY  
अभियन्त्रिकी विभाग  
ENGINEERING DEPARTMENT

NIQ No. RCB/04-02/95/NIQ-12/2020-21

Date 28.12.2020

**NOTICE INVITING QUOTATIONS**

**Name of Work:** Installation and fixing of 1.5 TR Split AC at lab No. C 211 & C 311 in 3<sup>rd</sup> wing at RCB Building, NCR Biotech Science Cluster, 3<sup>rd</sup> Milestone, Faridabad-Gurgaon Expressway, Faridabad.

Sealed spot quotation are invited from the experienced contractor dealing in installation of Split Air Conditioners for **Installation and fixing of 03 Nos X 1.5 TR Split AC** at RCB Building, NCR Biotech Science Cluster, Faridabad. As per "Schedule of work".

**TERMS AND CONDITIONS**

1. Installation of Split AC as per Schedule of Work, specification and instruction of Engineer-In-charge.
2. Vender are advised to visit the site before submitting quotation.
3. **Sealed quotation should be dropped in the tender box kept at RCB reception on 07.01.2021 upto 14.00 PM.**
4. AC Out door Units of Havels Make, will be installed on RCB building's on exterior wall existing MS structure at approx 8 Mtr. Height. The job includes Making holes through wall for pipes etc repairing and making the affected wall good.
5. No Advance payment shall be made.
6. Payment will be made as per actuals.
7. Triplicate pre-receipted invoice should be submitted by agency with revenue ticket of ₹1/-
8. Income tax shall be deducted from bill as per GOI rules for which contractor/supplier should have a **PAN No. and GST No.** in the name of registered company of proprietor for depositing TDS.
9. The rate should be inclusive of labour, freight, cartage, loading-unloading and fixing etc. GST part should be shown separately.
10. Time allowed for completion for work shall be 17 days from date of issue of Work order.
11. Schedule of work should be print on letterhead and submit at office of Executive Engineer, RCB.
12. Contractor will be responsible for safety and insurance of its workers.

(R K Rathore)  
Executive Engineer

NIQ NO- RCB/04-02/95/NIQ-12/2020-21

**Price Bid**

**Name of Work:** Installation and fixing of 1.5 TR Split AC at lab no. C 211 & C 311 in 3<sup>rd</sup> wing at RCB Building, NCR Biotech Science Cluster, 3<sup>rd</sup> Milestone, Faridabad-Gurgaon Expressway, Faridabad.

SL. No	Description	Qty	Unit	Rate	Amount
1	Installation and Fixing of 1.5 TR Split AC. Outdoor unit should be fixed on existing MS structure frame with nut bolt and washer. Weight of ODU Appx-32 Kg	3	Nos		
2	<b>Additional Items</b>				
2 a	Copper pipe set for HP/LP refrigerant for Split units duly insulated and tapped should be properly fixed & aligned on exterior wall. .	80	Ft		
2 b	Waste water drain Pipe 25 mm PVC, insulated with nitrile rubber should be properly fixed & aligned on exterior wall or as per requirement	100	Ft		
2 c	Interconnecting electrical cable 3 Core x 2.5 Sqm FR muti strand copper cable between indoor & outdoor units Make Havels / Polycab/ Finolex / KEI / ISI Mark	30	Rmt		
2 d	Providing and fixing double scaffolding system (cup lock type) on the exterior side, up to seven story height made with 40 mm dia M.S. tube 1.5 m centre to centre, horizontal & vertical tubes joining with cup & lock system with M.S. tubes, M.S. tube challies, M.S. clamps and M.S. staircase system	80	Sqm		

	<p>in the scaffolding for working platform etc. and maintaining it in a serviceable condition for the required duration as approved and removing it thereafter .The scaffolding system shall be stiffened with bracings, runners, connection with the building etc wherever required for inspection of work at required locations with essential safety features for the workmen etc. complete as per directions and approval of Engineer in-charge. The elevational area of the scaffolding shall be measured for payment purpose. The payment will be made once irrespective of duration of scaffolding.</p>				
Total					
SGST			.....%		
CGST			.....%		
IGST			.....%		
GR. Total					

Reasonable and competitive rate quotation should be submitted by agency.

(Signature of the bidder)

Name:

Place:

Seal